



**LEVEL 1  
TRANSPORTATION  
MANAGEMENT  
PLAN**

**SIGNIFICANT  
PROJECT**

Project Name: **Route 146 Corridor Interchange Improvements**

RI Design Contract No(s): **2008-EH-006**

RI Construction Contract No(s): **2011-CH-043**

Municipalities: **Providence, North Providence, Lincoln, North Smithfield**

Submission: **90%**      Date: **10-Mar-2011**



**TABLE OF CONTENTS**

Section Title	Page Number
<b>TMP Roles and Responsibilities.....</b>	<b>2</b>
<b>Project Information.....</b>	<b>6</b>
Traffic Conditions Prior to Start of Work.....	8
Expected Traffic Conditions During the Work.....	9
<b>Transportation Management Strategies</b>	
Traffic-Related Work Restrictions.....	10
Temporary Traffic Control Plans.....	11
Public Information Plan.....	12
Transportation Operations Plan.....	13
Performance Monitoring Plan.....	14
<b>Changes to TMP &amp; Contingency Plans.....</b>	<b>15</b>
<b>TMP Approvals.....</b>	<b>15</b>
<b>List of Attachments.....</b>	<b>16</b>

## TMP ROLES AND RESPONSIBILITIES

### TMP Development Managers

*Project design managers who oversee the development of this TMP*

RIDOT	
Name:	John Smith, P.E.
Title:	Principal Civil Engineer
Unit:	Traffic Design Section
Office Phone:	401-222-4046 x0001
Mobile Phone:	401-123-4567
E-Mail:	<a href="mailto:jbsmith@dot.ri.gov">jbsmith@dot.ri.gov</a>

CONSULTANT	
Name:	Michael Signals, P.E., PTOE
Title:	Senior Traffic Engineer
Company/Unit:	ABC Consultants, Inc.
Office Phone:	401-987-6543
Mobile Phone:	401-555-5555
E-Mail:	<a href="mailto:msig00@ABC.com">msig00@ABC.com</a>

### TMP Implementation Managers

*Project construction managers with the primary responsibility & authority for implementation of this TMP*

RIDOT	
Name:	
Title:	
Unit:	
Office Phone:	
Mobile Phone:	
E-Mail:	

CONTRACTOR	
Name:	
Title:	
Company/Unit:	
Office Phone:	
Mobile Phone:	
E-Mail:	

### TMP Implementation Task Leaders

*Other parties responsible for completing specific transportation management tasks required by this TMP*

NAME / TITLE (if individual is named)	COMPANY / UNIT	PHONE	E-MAIL
	RIDOT / TMC	401-222-5826	<a href="mailto:tmc_operations@dot.ri.gov">tmc_operations@dot.ri.gov</a>
Task Description / Responsibilities:	To be contacted via RIDOT notification form (FAX to 222-4225 / 222-5640) min. 48 hours prior to the implementation of lane closures and detours. Will update RIDOT 511 system as necessary.		
	RIDOT / Communications	401-222-1362	<a href="mailto:webmaster@dot.ri.gov">webmaster@dot.ri.gov</a>
Task Description / Responsibilities:	To be contacted via RIDOT notification form (FAX to 222-3905) min. 48 hours prior to the implementation of lane closures and detours. Will update/issue RIDOT travel advisories web site / news releases as necessary.		
	RIDOT / Customer Service	401-222-2450	<a href="mailto:CustomerService@dot.ri.gov">CustomerService@dot.ri.gov</a>
Task Description / Responsibilities:	To be contacted via RIDOT notification form (FAX to 222-5648) min. 48 hours prior to the implementation of lane closures and detours. If necessary, will assist in coordinating the strategies included in the Public Information Plan.		
Joseph Bucci, P.E.	Managing Engineer	RIDOT / Traffic Management	401-222-5826 x4200
Task Description / Responsibilities:	Responsible for obtaining/archiving work zone crash data each week and for collecting traffic counts during Phase 4 of the project (see Performance Monitoring Plan for details).		

## TMP Implementation Task Leaders (continued)

NAME / TITLE (if individual is named)	COMPANY / UNIT	PHONE	E-MAIL
Task Description / Responsibilities:			
Task Description / Responsibilities:			
Task Description / Responsibilities:			
Task Description / Responsibilities:			
Task Description / Responsibilities:			
Task Description / Responsibilities:			
Task Description / Responsibilities:			
Task Description / Responsibilities:			
Task Description / Responsibilities:			
Task Description / Responsibilities:			
Task Description / Responsibilities:			
Task Description / Responsibilities:			
Task Description / Responsibilities:			
Task Description / Responsibilities:			
Task Description / Responsibilities:			
Task Description / Responsibilities:			
Task Description / Responsibilities:			

## TMP Stakeholder Contacts

*TMP Stakeholders to be consulted or coordinated with during the work*

NAME / TITLE (if individual is named)	COMPANY / UNIT	PHONE	E-MAIL
Role / Notification/Consultation Requirements:			
Role / Notification/Consultation Requirements:			
Role / Notification/Consultation Requirements:			
Role / Notification/Consultation Requirements:			
Role / Notification/Consultation Requirements:			
Role / Notification/Consultation Requirements:			
Role / Notification/Consultation Requirements:			
Role / Notification/Consultation Requirements:			
Role / Notification/Consultation Requirements:			
Role / Notification/Consultation Requirements:			
Role / Notification/Consultation Requirements:			
Role / Notification/Consultation Requirements:			
Role / Notification/Consultation Requirements:			
Role / Notification/Consultation Requirements:			
Role / Notification/Consultation Requirements:			
Role / Notification/Consultation Requirements:			
Role / Notification/Consultation Requirements:			
Role / Notification/Consultation Requirements:			
Role / Notification/Consultation Requirements:			
Role / Notification/Consultation Requirements:			
Role / Notification/Consultation Requirements:			
Role / Notification/Consultation Requirements:			
Role / Notification/Consultation Requirements:			
Role / Notification/Consultation Requirements:			
Role / Notification/Consultation Requirements:			
Role / Notification/Consultation Requirements:			

## Emergency Service Contacts

*Emergency service agencies/providers expected to be impacted by the project work zones*

NAME / TITLE (if individual is named)	AGENCY / UNIT	PHONE	E-MAIL
	Rhode Island State Police	401-444-1000	
Special Details / Requirements:			
	ABC Ambulance Co.	401-243-8900	
Special Details / Requirements:			
	Providence Police Department	401-272-3121	
Special Details / Requirements:			
	Providence Fire Department	401-243-6060	
Special Details / Requirements:			
	N. Providence Police Department	401-231-4533	
Special Details / Requirements:			
	N. Providence Fire Department	401-231-8505	
Special Details / Requirements:			
	Lincoln Police	401-333-1111	
Special Details / Requirements:			
	Licoln Fire (Albion District)	401-333-1242	
Special Details / Requirements:			
	North Smithfield PD	401-762-1213	
Special Details / Requirements:			
Special Details / Requirements:			
Special Details / Requirements:			
Special Details / Requirements:			
Special Details / Requirements:			
Special Details / Requirements:			

## PROJECT INFORMATION

### Brief Project Description

This project is for the partial and full reconstruction and rehabilitation of seven highway interchanges on Route 146 in the Cities/Towns of Providence, North Providence, Lincoln, and North Smithfield, Rhode Island. The project includes, but is not limited to, the construction of new ramps to/from Route 146; the realignment of existing ramps; intersection improvements; [complete description here].

### General Work Limits

The work will take place along the Route 146 corridor in several discontinuous areas affecting both (1) mainline and entering/exiting vehicle traffic on Route 146 and I-95 and (2) all types of road users on principal arterial roadways intersecting Route 146.

While some work will be completed outside of existing roadway limits with no impact to road users, other portions of the work will require temporary restrictions of traffic, including lane closures, shoulder closures, lane shifts, road/ramp closures, and detours. The duration of each such restriction will vary depending on the work operation, and will range from long-term (e.g., stationary lane shifts for construction of ramps) to short-term (e.g., mobile lane closures for installation of pavement markings).

### WORK ZONE LOCATIONS

ROADWAY NAME or INTERSECTION	FROM	TO	APPROX. LENGTH
Route 146	I-95 (Providence)	Route 146A (N. Smithfield)	15 mi.
Sayles Hill Road	At Route 146 Intersection		200 ft.
Interstate 95	Smith Street (US 44)	Industrial Drive	3/4 mi.
Old Sayles Hill Road	At Route 146 Ramps		1,000 ft.
Admiral Street	At Route 146 Ramps		100 ft.
Mineral Spring Avenue (Route 15)	At Route 146 Ramps		700 ft.
Charles Street (Route 246)	At Route 146 Ramps		200 ft.
Washington Highway (Route 116)	At Route 146 Ramps		700 ft.

## General Project Schedule & Construction Sequence\*

The project is expected to begin in Spring of 2011 and be completed in Fall of 2012.

Most drainage and utility work will be completed first, followed by the construction of new facilities outside of existing roadway limits, then work to tie-in new highway ramps with existing roadways (including reconstruction/resurfacing of existing roadway approaches and intersection improvements).

The recommended construction sequence with anticipated completion dates is as follows:

PHASE	DESCRIPTION	ANTICIPATED COMPLETION DATE
Phase 1A	Utility Work - NG	June 15, 2011
Phase 1B	Utility Work - VZ	July 1, 2011
Phase 1C	Preliminary Drainage	July 15, 2011
Phase 2A	I-95 / Mineral Spring Ramp Construction	June 15, 2012
Phase 2B	Route 116 Ramp Construction	July 15, 2012
Phase 3A	Sayles Hill Road Reconstruction	August 30, 2012
Phase 3B	Old Sayles Hill Road Reconstruction	October 1, 2012
Phase 4A	Route 116 / Mineral Spring Completion	September 15, 2012
Phase 4B	Sayles Hill Road Final Tie-In	October 1, 2012
Phase 5A	I-95 / Charles / Admiral Street Reconstruction	October 15, 2012
Phase 5B	I-95 / Charles / Admiral Street Final Tie-In	November 10, 2012

\*The information in this section is not intended to and shall not supersede the approved schedule and milestone/completion dates for the project.

OTHER ACTIVITIES IN PROJECT VICINITY WITH POTENTIAL FOR CAUSING SIGNIFICANT CUMULATIVE IMPACTS	
ACTIVITY	DETAILS / DATES / LOCATIONS
I-95 Interchange Project (2008-CH-019)	Project will be under construction until Summer 2011. Resurfacing and ramp realignment work extends to Bridge No. 045901 on Route 146 N-Bnd and S-Bnd.

## TRAFFIC CONDITIONS PRIOR TO START OF WORK

### Traffic Data

---

*[summarize appropriate data here]*

### Intersection Control

---

*[summarize appropriate data here]*

### Crash Data

---

*[summarize appropriate data here]*

### Local Community Issues and Concerns

---

Commercial developments at the Route 116 Interchange have demanded that access/egress to/from sites be maintained during the work.

ABC Elementary School in North Providence has requested that work be restricted on Mineral Spring Avenue from September - June in order to avoid noise disruptions.



## EXPECTED TRAFFIC CONDITIONS DURING THE WORK

### Traffic Data

---

*[summarize appropriate data here]*

### Anticipated Demands from Other Activities in Vicinity of Project

---

## TRAFFIC-RELATED WORK RESTRICTIONS

### General Restrictions

The Contractor shall maintain two 11-foot minimum width travel lanes in each direction open to traffic at all times on Route 146 unless otherwise noted below. One 11-foot minimum width travel lane must remain open to traffic at all times on all Route 146 ramps unless otherwise noted below.

On Route 146 and I-95, lane closures will not be allowed on weekdays between 6:00 am and 8:00 pm. On all other roadways, lane closures will not be allowed on weekdays between 6:00 am and 9:00 am and between 3:00 pm and 7:00 pm.

On Route 146, I-95, and their adjoining ramps, shoulder closures will not be allowed on weekdays between 6:00 am and 9:00 am and between 3:00 pm and 7:00 pm.

Full closures of either direction of Route 146 will only be allowed during blasting operations and when the appropriate detours shown on the Plans are in place and accepted.

Ramps 146-A and 146-B shall be opened to traffic prior to beginning demolition of the existing I-95 ramps.

No work of any kind shall take place on Friday and Saturday nights between 7:00 pm and 6:00 am the following morning.

No work on Mineral Spring Avenue and/or its adjoining Route 146 ramps shall take place on school days between 7:00 am and 3:30 pm.

The Contractor shall maintain at least one 11-foot minimum width travel lane in each direction open to traffic at all times on Washington Highway (Route 116), Mineral Spring Avenue (Route 15), Charles Street (Route 246), and Sayles Hill Road.

Temporary turn lanes for site driveways on Route 116 as called for on the Plans shall be installed prior to beginning demolition of Ramp 146-P.

### Holiday Restrictions

#### 2011 HOLIDAY WORK SCHEDULE

Independence Day - No night work on Sunday, July 3 and no day or night work on Monday, July 4.

Victory Day - No day or night work from Saturday, August 6 through Monday, August 8.

Labor Day - No day or night work from Saturday, September 3 through Monday, September 5.

Columbus Day - No day or night work from Saturday, October 8 through Monday, October 10.

Veterans Day - No day or night work from Thursday, November 10 through Friday, November 11.

Thanksgiving Day - No day or night work from Wednesday, November 23 through Sunday, November 27.

#### 2012 HOLIDAY WORK SCHEDULE

Easter - No night work Saturday, April 7 and no day or night work on Sunday April 8.

Memorial Day - No day or night work from Saturday, May 26 through Monday, May 28.

Independence Day - No night work on Tuesday, July 3 and no day or night work on Wednesday, July 4.

Victory Day - No day or night work from Saturday, August 11 through Monday, August 13.

Labor Day - No day or night work from Saturday, September 1 through Monday, September 3.

Columbus Day - No day or night work from Saturday, October 6 through Monday, October 8.

All Friday daytime work on any holiday weekend must end by 1:00 p.m.

If the Contract is extended beyond the specified completion date, a similar set of holiday work restrictions will be established by the Engineer.

## TEMPORARY TRAFFIC CONTROL PLANS

*These RIDOT- and/or Designer-Developed TTC Plans will be used during the work on this project*

RIDOT-DEVELOPED TYPICAL TTC PLANS		Included in:	
		TMP	Plan Set
<input type="checkbox"/>	Mobile Operation	<input type="checkbox"/>	<input type="checkbox"/>
<input type="checkbox"/>	Work Beyond the Shoulder	<input type="checkbox"/>	<input type="checkbox"/>
<input checked="" type="checkbox"/>	Shoulder Closure - Two Lane Road	<input type="checkbox"/>	<b>X</b>
<input checked="" type="checkbox"/>	Shoulder Closure - Limited Access	<input type="checkbox"/>	<b>X</b>
<input type="checkbox"/>	1-Side Lane Shift - Two Lane Road	<input type="checkbox"/>	<input type="checkbox"/>
<input type="checkbox"/>	2-Side Lane Shift - Two Lane Road	<input type="checkbox"/>	<input type="checkbox"/>
<input type="checkbox"/>	Lane Shift - Limited Access	<input type="checkbox"/>	<input type="checkbox"/>
<input checked="" type="checkbox"/>	Lane Closure - Two Lane Road	<input type="checkbox"/>	<b>X</b>
<input type="checkbox"/>	Lane Closure - Four Lane Road	<input type="checkbox"/>	<input type="checkbox"/>
<input checked="" type="checkbox"/>	Lane Closure - Limited Access	<input type="checkbox"/>	<b>X</b>
<input type="checkbox"/>	Double Lane Closure - Limited Access	<input type="checkbox"/>	<input type="checkbox"/>
<input type="checkbox"/>	Others (list) -	<input type="checkbox"/>	<input type="checkbox"/>

DESIGNER-DEVELOPED TTC PLANS		Included in:	
		TMP	Plan Set
	TTC Plan No. 1: Phase 1A Construction	<input type="checkbox"/>	<b>X</b>
	TTC Plan No. 2: Phase 1B Construction	<input type="checkbox"/>	<b>X</b>
	TTC Plan No. 3: Phase 1C Construction	<input type="checkbox"/>	<b>X</b>
	TTC Plan No. 4: Phase 2A & 3A Construction	<input type="checkbox"/>	<b>X</b>
	TTC Plan No. 5: Phase 2B & 3B Construction	<input type="checkbox"/>	<b>X</b>
	TTC Plan No. 6: Phase 4A Construction	<input type="checkbox"/>	<b>X</b>
	TTC Plan No. 7: Phase 4B Construction	<input type="checkbox"/>	<b>X</b>
	TTC Plan No. 8: Phase 5A Construction	<input type="checkbox"/>	<b>X</b>
	TTC Plan No. 9: Phase 5B Construction	<input type="checkbox"/>	<b>X</b>
	TTC Plan No. 10: Detour Plan A	<input type="checkbox"/>	<b>X</b>
	TTC Plan No. 11: Detour Plan B	<input type="checkbox"/>	<b>X</b>
	TTC Plan No. 12: Typical Temporary Traffic Control Plans	<input type="checkbox"/>	<b>X</b>
	TTC Plan No. 13: Roundabout Phased Construction	<input type="checkbox"/>	<b>X</b>
	TTC Plan No. 14: I-95 / Route 146 Resurfacing Operations	<input type="checkbox"/>	<b>X</b>
		<input type="checkbox"/>	<input type="checkbox"/>
		<input type="checkbox"/>	<input type="checkbox"/>
		<input type="checkbox"/>	<input type="checkbox"/>
		<input type="checkbox"/>	<input type="checkbox"/>
		<input type="checkbox"/>	<input type="checkbox"/>
		<input type="checkbox"/>	<input type="checkbox"/>



# TRANSPORTATION OPERATIONS PLAN

*These strategies will be used to provide improved transportation operations/safety within project work zones*

## Corridor/Network Management Strategies

SELECTED STRATEGIES	RESPONSIBILITIES / REQUIREMENTS / SPECIAL CONSIDERATIONS
Signal timing/coordination improvements	Described in Job Specific Specification T20.9906
Street/intersection improvements	New turn lanes for businesses on Route 116 in Lincoln to be installed prior to Phase 4, all as shown on Plans.

## Work Zone Safety Management Strategies

SELECTED STRATEGIES	RESPONSIBILITIES / REQUIREMENTS / SPECIAL CONSIDERATIONS
Road safety audits (design)	An RSA was completed during Preliminary Design; RSA recommendations incorporated into Plans.
Crash attenuators	To be installed at locations shown on TTC plans.
Temporary traffic barrier	To be installed at locations shown on TTC plans.

## Traffic/Incident Management & Enforcement Strategies

SELECTED STRATEGIES	RESPONSIBILITIES / REQUIREMENTS / SPECIAL CONSIDERATIONS
RIDOT Transportation Management Center	RIDOT TMC operators, using existing CCTV cameras, will coordinate and manage traffic and incidents in and around the project work zones.
Establish available local detour routes	Locally-approved alternate detour routes (using local roadways) are shown on the TTC plans. Only to be used if prior approval is obtained from the RIDOT Chief Engineer and proper notifications are given to municipalities.
Dedicated (paid) police enforcement	State Police to provide targeted speed monitoring on Route 146 during Phases 1, 3, and 4 of the project, all in accordance with the State Agreement dated April 18, 2008 (attached).

## Demand Management Strategies

SELECTED STRATEGIES	RESPONSIBILITIES / REQUIREMENTS / SPECIAL CONSIDERATIONS
Transit service improvements	RIDOT/RIPTA is constructing a new bus terminal on Route 116 under RIC 2008-CE-001 in an effort to increase transit ridership along this principal arterial.

# PERFORMANCE MONITORING PLAN

## General Monitoring Requirements

The **Contractor's TMP Implementation Manager** is responsible for keeping the portion of the project being used by public traffic in a condition that (1) safely and adequately accommodates such traffic and (2) is in accordance with the Traffic-Related Work Restrictions, the Temporary Traffic Control Plans, and where appropriate, the other transportation management strategies identified above.

The **RIDOT TMP Implementation Manager** or his/her responsible designee should (1) inspect the project work zones at initial setup, at the start of each subsequent work day, and just prior to extended breaks in the work (e.g., weekends) for conformance with the Temporary Traffic Control Plans, the *ATSSA Quality Guidelines for Temporary Traffic Control Devices and Features*, and where applicable, the other transportation management strategies identified above and (2) document all work zone-related feedback and complaints that are received from the public.

## Project-Specific Performance Monitoring Strategies

### SELECTED STRATEGIES

Team meetings

### RESPONSIBILITIES / REQUIREMENTS / SPECIAL CONSIDERATIONS

The RIDOT TMP Implementation Manager will meet with the Construction Management Chief, the State Traffic Engineer, and the Traffic Management Chief on a regular basis to discuss and assess the safety and mobility impact of the project work zones to date. At these meetings, attendees will discuss how well the TMP is managing the project impacts and will verify that all appropriate stakeholders and project officials have been receiving timely notifications where required.

Surveillance: Traffic counts

The RIDOT Traffic Management Section will conduct turning movement (AM & PM Peak Periods) and tube counts at the major ramps at the Route 116 Interchange before each major Subphase of Phase 4 (A thru E). This data will be summarized and shared with the RIDOT TMP Implementation Manager, the State Traffic Engineer, and the Consultant TMP Development Manager.

Surveillance: Traffic queues/delays

The Consultant TMP Development Manager will arrange to monitor and record vehicle queue lengths at the Route 146 @ Sayles Hill Road intersection during Phase 4 and Phase 5, at the times and durations listed in the approved proposal for the project Design Contract (attached).

Surveillance: Travel times

The Consultant TMP Development Manager will arrange to conduct weekday PM peak period probe vehicle travel time runs during Phase 2 of this project, at the frequency and within the limits all as listed in the approved proposal for the project Design Contract (attached). The travel time data will be forwarded to the RIDOT TMP Implementation Manager the morning following each day it is collected.

Assessment: Mobility

The Consultant TMP Development Manager will analyze traffic delays at the signalized ramp intersections during Phase 4 of this project using the traffic count data collected by the RIDOT Traffic Management Section, all at the frequency and within the limits listed in the approved proposal for the project Design Contract (attached). The results of the analyses will be documented in a brief report and forwarded to the State Traffic Engineer and the RIDOT TMP Implementation Manager.

**CHANGES TO TMP & CONTINGENCY PLANS**

If at any time (1) a significant deviation from any of the strategies included in the TMP (e.g., the use of an alternate construction sequence) is desired by one or more members of the project implementation team, (2) field observations and/or data suggest that impacts to road users are or will be unacceptable, or (3) one or more performance requirements established in the TMP are not being met in the field, the RIDOT TMP Implementation Manager shall report the situation to his/her supervisor or Division/Section/Unit manager. The supervisor / manager will coordinate with the State Traffic Engineer, the Traffic Management Chief, the TMP Development and/or Implementation Manager(s), the Chief Engineer, and/or other interested parties as appropriate and/or necessary to consider and determine whether revised and/or alternate strategies should be implemented in an effort to lessen the adverse safety and/or mobility impacts of the project. If the supervisor / manager deems that strategy changes should be implemented, the changes shall be documented in a revised version of the TMP and the Traffic Management Chief, the State Traffic Engineer, and the Chief Engineer must approve of the revised TMP prior to their implementation.

If a significant deviation from any of the strategies included in the TMP is requested by the Contractor, unless directed otherwise by the RIDOT the Contractor is responsible for preparing and submitting to the RIDOT TMP Implementation Manager appropriate documentation (e.g., design calculations, analysis reports, Temporary Traffic Control Plans, etc.) showing that the requested change(s) are (1) feasible and (2) expected to result in safety and mobility impacts that are no more adverse than the impacts resulting from the strategies already included in the latest approved TMP. The RIDOT will review and consider the submittal(s) as described in the preceding paragraph and will determine whether the changes should be implemented. If the requested changes are approved by the RIDOT, unless otherwise directed by the RIDOT the Contractor shall prepare and submit to the RIDOT TMP Implementation Manager a revised version of the latest approved TMP in both printed and electronic (Microsoft® Excel) format that documents all of the approved changes. Work to implement the changes shall not begin until the Traffic Management Chief, the State Traffic Engineer, and the Chief Engineer have approved of the revised TMP.

When unexpected events (e.g., crashes, inclement weather, unforeseen traffic demands, etc.) occur in a project work zone where one or more lanes are closed, the RIDOT TMP Implementation Manager or his/her responsible designee should (1) determine whether or not the lane closure(s) can/should be removed in order to improve traffic operations and/or minimize delays and (2) if deemed appropriate, take action to remove the lane closure(s).

**Project Specific Contingencies**



**TMP APPROVALS**

*All approvals must be obtained prior to start of work*

TRAFFIC MANAGEMENT CHIEF		
Signature: _____		
Date: _____		
Revision #	Initials	Date

STATE TRAFFIC ENGINEER		
Signature _____		
Date _____		
Revision #	Initials	Date

CHIEF ENGINEER		
Signature: _____		
Date: _____		
Revision #	Initials	Date

**LIST OF ATTACHMENTS**

